National Catastrophe Team

P.O. Box 672041
Dallas, Texas 75267
Phone: (800) 547-8676
Fax: (888) 859-3946

PATRICIA_GILLIARD-SM

Source - Eagle View

Source - Eagle View



Dwelling Roof

1902.27 Surface Area
219.15 Total Perimeter Length
19.02 Number of Squares
55.44 Total Ridge Length

DESCRIPTION	QUANTITY	UNIT	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
5. Digital satellite system - Detach & reset	1.00 EA	23.83	23.83	0/NA	Avg.	50% [%]	(11.92)	11.91
1. Remove 3 tab - 20 yr. - composition shingle roofing - incl. felt	19.02 SQ	40.29	766.32	0/20 yrs	Avg.	NA [%]	(0.00)	766.32
3. 3 tab - 20 yr. - comp. shingle roofing - w/out felt	20.67 SQ	147.18	3,042.21	0/20 yrs	Avg.	50% [%]	(1,521.11)	1,521.10
Auto Calculated Waste: 8.7%, 1.65SQ								
Options: Valleys: Closed-cut (half laced), Include eave starter course: Yes, Include rake starter course: No, Include ridge/hip cap: Yes, Exposure: 5", Bundle Rounding: 0.1%, 0.01SQ - (included in waste calculation above)								
4. Roofing felt - 15 lb.	19.02 SQ	22.93	436.13	0/20 yrs	Avg.	50% [%]	(218.07)	218.06
6. Continuous ridge vent - aluminum	50.00 LF	6.73	336.50	0/35 yrs	Avg.	50% [%]	(168.25)	168.25
7. Flashing - pipe jack	4.00 EA	31.65	126.60	0/35 yrs	Avg.	50% [%]	(63.30)	63.30
15. Flashing - rain diverter	1.00 EA	30.76	30.76	0/35 yrs	Avg.	50% [%]	(15.38)	15.38
16. R&R Chimney flashing - average (32" x 36")	1.00 EA	312.81	312.81	0/35 yrs	Avg.	50% [%]	(149.41)	163.40
Totals: Dwelling Roof			**5,075.16**				**2,147.44**	**2,927.72**



Shed 1

116.93 Surface Area
43.99 Total Perimeter Length
1.17 Number of Squares
13.00 Total Ridge Length

DESCRIPTION	QUANTITY	UNIT	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
No storm damage								
Totals: Shed 1			**0.00**				**0.00**	**0.00**